

ECOWAS Regional Workshop on WIND ENERGY

First Large Scale Wind Energy PPP in Sub-Saharan Africa

CABEÓLICA
05 November 2013

Investors




Lenders





History:

- Prior to Cabeólica only 2.4 MW wind capacity connected to national grid network.
- Government sought expansion of wind energy capacity for over 10 years.
- The aspirations of the Government of Cape Verde and the need for foreign investment and technical and business know-how, resulted in the dynamic Cabeólica PPP.





Background of the company:

- In 2008 this strong PPP was established between a Developer - InfraCO Lda; GoCV and Electra, that had the purpose of implementing an economically feasible alternative for the rapidly growing energy sector.
- In 2010 a PPA was signed with the Off-taker.
- Africa Finance Corporation and Finnish Fund for Industrial Cooperation joined as investors in 2010.
- European Investment Bank and Africa Development Bank entered as long-term Lenders in 2010.
- Construction initiated at the end of 2010 and was completed by mid 2012 and the wind farms began commercial operation as follows:
 - Santiago – November 2011
 - São Vicente – November 2011
 - Sal – February 2012
 - Boa Vista – July 2012





The Cabeólica Company:

- Cape Verdean company that constructed and currently operates four wind farms, with a total installed capacity of 25.5 MW.
 - Santiago – 9.35 MW;
 - São Vicente – 5.95 MW;
 - Sal - 7.65 MW;
 - Boa Vista – 2.55 MW.

- Currently contributing with roughly 20% of total energy consumption in Cape Verde.

- Playing an important role in the Government's established renewable energy targets.

- Has the strategic objectives of
 - Reducing oil based electricity generation;
 - Attract private investment;
 - Relieving State of alone financing the country's energy sector.





Public Private Partnership:

- The PPP administers the development, financing, construction, ownership and operation of the four wind farms for wind production under an independent producer regime.
- Experienced developers created the dynamics behind the financing of the project by identifying investors to take the risk of investment and assume a shareholding position, as well as, identifying international institutions to assume the financing.
- Provided essential Government Support.
- Had positive influence on private financing and private companies investing in developing the electricity supply systems, thus providing additional financial and business know-how resources to complement the public sector resources.



Main Challenges:

- Development phase: time necessary to finalize all preliminary studies; agreements; land concessions; permit and licenses; and contractual and legal documentation.
- Conceptual design: a dynamic power analysis of four completely different power grids, each with its own complex issues, had to be conducted to assess the limitations and evaluate wind energy integration.
- Implementation phase: transportation of 30 turbines to different islands with logistic limitations and equipment and personnel for in land specialized works.
- Operating phase: sudden transition from almost 100% diesel to a diesel-wind grid connected system posed challenges related to grid stability, dispatching of power generated by different sources and personnel capacitation.





Financial Aspects:

○ Project Finance Structure

- Investment based on a project finance scheme: 30% equity and 70% debt provided, in a total project amount of +/- 60 M Euros

○ Essential Instruments

- PPA - Take or Pay.
- Support Agreement - Escrow Account (essential to attract external investors and debt providers).
- Development and Investment Agreement between Investors
- Common Terms Agreement with the Lenders (requirements).
- EPC contract with Vestas for the implementation of 30 V-52 turbines.
- SAA contract to guarantee performance.






Economic Benefits:


- Tariffs stable and lower than current conventional production costs.
- Estimated savings for the utility company/country at a total of EUR 3 million.
- Reduced oil imports for energy production reduces the Country sensitivity to commodity prices and improves the trade balance.
- EUR 60 million of investment made with no public funding.



Energy Invoiced



Electricity Invoiced Jan. to Sep. 2013 in Santiago , S.V. and Sal





Cabeólica Technical Performance

- The wind farms significantly increased availability of power.
- As of October 2013 the wind farms had generated a total of 138,000 MWh.
- This translates to roughly 20% of the total supply in Cape Verde.

Total Energy Production			
Site	2012	2013	%
Santiago	22.201	25.716	14%
S. Vicente	16.198	17.649	8%
Sal	8.253	13.301	38%
Boavista *	3.083	3.829	19%
Total	49.734	60.496	18%


* Operation started in April 2012






Wind Speed - monthly distribution

WIND SPEED - SANTIAGO WF



- Average wind speed: 8m/s
- 73%: above 6m/s
- Above 60%: N – NNE


WIND SPEED - S. VICENTE WF



- Average wind speed: 9,5m/s
- 80%: above 6m/s
- Above 80%: NNE - NE




WIND SPEED - SAL WF



- Average wind speed: 8,5m/s
- 78%: above 6m/s
- Above 50%: NE – ENE

WIND SPEED - BOAVISTA WF



- Average wind speed: 7,8m/s
- 70%: above 6m/s
- Above 55%: NE – ENE



○ Energy Available

• **Curtailment of the wind farms through set point**

- Santiago: set point released since February 2013;
- S. Vicente: set point min- 2,5 MW (from 1AM to 6 AM);
- Sal: set point max - 3,4 MW
- Boa Vista: set point max - 1,3 MW.

• **Production challenges**


- Increase of Energy Production (5% - 2014);
- Keeping grid stability;
- Tests and fine tunings;
- Work with off-Taker to reduce events.

Energy Available			
Site	2012	2013	%
Santiago	25.988	26.300	1%
S. Vicente	23.131	24.191	4%
Sal	22.270	24.451	9%
Boavista *	5.499	7.169	23%
Total	76.887	82.110	6%


* Operation began in April 2012




Santiago Annual Hourly Average Power




S. Vicente Annual Hourly Average Power



Sal Annual Hourly Average Power



Boavista Annual Hourly Average Power





○ **Availability (first interim period)**

- Santiago – 99%
- S. Vicente – 97%
- Sal – 97%
- Boavista – 99%

○ **Capacity Factor**

	Capacity Factor	
	2012	2013
Santiago	33%	39%
S. Vicente	36%	41%
Sal	14%	24%
Boa Vista *	19%	21%


* Operation started in April 2012






PENETRATION RATE - SANTIAGO WF

35% Instantâneos




PENETRATION RATE - S. VICENTE WF

55% Instantâneos




PENETRATION RATE - SAL WF

50% Instantâneos



PENETRATION RATE - BOA VISTA WF

33% Instantâneos





Environmental Aspects:

- Thorough Environmental and Social Impact Assessment (ESIA) in line with local laws and World Bank environmental standards.
- Public consultation in all four islands.
- Set the highest possible standard in environmental assessment which will set an important precedent for future projects.
- Elaboration of a detailed Environmental Management Program (“ESMP”) which will be implemented throughout the 20 year expected lifetime.
- Comprehensive long-term conservation work for local endemism such as Birds and reptiles.

Company progressing in line with obligations set in the ESIA and ESMP.





Environmental and Social Benefits:

- Wind farm production has offset diesel imports by over 22,000 Tonnes.
- Curbed over 85,000 tonnes of GHG emissions to date, thus aiding in achieving international environmental obligations.
- Project is staffed entirely by Cape Verdeans thus ensuring retention of know-how.
- Environmental education work in schools.
- Various studies financed by Cabeólica on relevant endemic species

Strict Health and Safety standards in place resulting in 0 accidents to date.





Clean Development Mechanism:

- Advantages:
 - Additional funds for projects
 - First CDM project in Cape Verde –structure is set which is an attraction for other CER and VER Projects.
- Disadvantages
 - Long registration periods – **took Cabeólica 3 years to register**
 - Great resources associated with validation such as costs
 - Highly volatile market





Clean Development Mechanism:

- Process of Registration
 - Development of a Project Design Document (PDD)
 - Key technical document describing the project
 - Contains calculation of estimated carbon credits according to CDM methodology.
 - Submission of approval letter by the Designated National Entity (DNA)
 - DNA of Cape Verde is Ministry of Environment
 - DNA must approve the project as in accordance with the country's sustainable development.
 - Validation from the Designated Operational Entity (DoE)
 - DoE = An independent auditor accredited by the UNFCCC
 - Validation assures the project meets requirements of the UNFCCC.
 - Final analysis of the CDM Executive Board.

Cabeólica was registered as a CDM project in October 2013 and to date has produced over 85,000 Emission Reduction Credits.





Replicability of the PPP:

- Cabeólica as the first large scale wind energy PPP in sub-Saharan Africa it has an important leadership role in encouraging other countries to launching of successful renewable energy PPPs.
- The PPP formula can work in countries with sufficient political will and serious and transparent environment between the public and private partners.
- The key ingredients for the success of the Cabeólica PPP are:
 - Participation of solid, transparent and high profile public and private partners
 - Government support
 - The incentive of a long term off take agreement to ensure predictable and transparent cost planning and predictable and transparent cash flow projections
 - Stable and reliable energy supply and continuous optimization of the commercial relationship with the Off-Taker.





Steps Forward:

- Spurred on by the success of Cabeólica, the GCV has set an ambitious target for 2020 (100% RE).
- Currently the local grid stability and spinning reserve requirements limit RE penetration to around 40-50%.
- The increase in uptake of renewable energy in general in Cape Verde will require maximization of stable production and minimization of losses through:
 - technical, commercial and organisational improvements
 - continuous development of the grid control systems
 - development of RE storage
 - training and continuing capacity building of personnel.





Acknowledgements:

- Cape Verde now boasts **one of the highest wind energy penetration rates in the world**. In 2011, the country was ranked third worldwide for total installed wind power per GDP.
- In 2011 Cabeólica won the **Best Renewable Project in Africa Award**, at the Africa Energy Award.
- In 2013 Cabeólica was recognized by IFC and Infrastructure Journal **as one of the top Public-Private Partnerships in Sub-Saharan Africa**.
- In 2013 Cabeólica **won the Ashden Awards** under the SIDS category for its achievements.



Thank you

Investors



Lenders

